


C SECTION



EARTH EXCAVATION FOR ENERGY DISSIPATING BASINS

THIS WORK INVOLVES THE EXCAVATION OF EARTH AS SHOWN IN THE DETAIL TO THE LENGTH, WIDTH, AND DEPTH DETERMINED BY THE ENGINEER. THE EARTH EXCAVATION WILL BE UTILIZIED IN THE ROADWAY EMBANKMENT OR WASTED AS DIRECTED BY THE ENGINEER.

THE EARTHWORK WILL NOT BE PAID FOR SEPARATELY. IT WILL BE CONSIDERED AS INCLUDED IN THE CONTRACT UNIT PRICE PER METRIC TON FOR "RIPRAP FOR STILLING BASIN".

ENERGY DISSIPATING BASINS SHALL BE CONSTRUCTED AT THE SAME TIME AS THE CULVERT OR DITCH.

ENERGY DISSIPATING BASINS ARE TO BE CONSTRUCTED AT LOCATIONS LISTED IN THE TABLE ON THIS SHEET AND AS SHOWN IN THE PLANS.

RIPRAP FOR ENERGY DISSIPATING BASINS


RIPRAP FOR ENERGY DISSIPATING BASINS SHALL BE CONSTRUCTED IN ACCORDANCE WITH SECTION 281 OF THE STANDARD SPECIFICATIONS.

THE LENGTH, WIDTH, AND DEPTH FOR RIPRAP PLACEMENT WILL BE DETERMINED BY THE ENGINEER.

THE RIPRAP MATERIAL SHALL MEET A QUALITY DESIGNATION OF A AS DEFINED IN SECTION 1005.01 OF THE STANDARD SPECIFICATIONS.


BEDDING MATERIAL WILL NOT BE REQUIRED.

FILTER FABRIC WILL BE PAID FOR AT THE CONTRACT UNIT PRICE PER SQUARE METER FOR "FILTER FABRIC".



CULVERT STATION	SIDE	LOCATION	DISSIPATOR POOL LENGTH m	APRON LENGTH m	WIDTH (W)	hs	TOP OF BERM hs + ye + 300 mm	RIPRAP THICKNESS		RIPRAP	RIPRAP FOR STILLING BASIN	FILTER FABRIC
								T ₁	T ₂	CLASS	m ton	sm
36+711.6	RT	FAP 310	21.0	10.7	26.8	2.1	2.7	1.2	0.9	A-6	1674.8	733.7
37+371.1	RT	FAP 310	20.7	10.4	35.2	2.1	4.2	1.2	0.9	A-6	2364.6	1034.8
37+942.6	LT	FAP 310	10.6	5.3	26.6	1.6	3.5	1.2	0.9	A-6	1037.0	450.1
38+143.5	RT	FAP 310	10.7	*	15.9	1.1	2.1	0.9	0.6	A-5	277.7	181.8
39+700.0	LT	FAP 310	6.2	3.1	12.0	0.6	1.8	0.7	0.5	A-4	134.6	106.6
0+150.0	RT	RAMP F	8.1	4.0	13.5	0.8	1.7	0.7	0.5	A-4	192.2	151.6

* NOT APPLICABLE - SEE CROSS SECTION



F.A.P. RTE.

STA.

SECTION

310 60-15, 60-15B

COUNTY

FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT

MADISON

SHEETS NO.

474

CONTRACT NO. 76323

NOTE A:

TRANSITION BASIN TO CONFORM TO THE NATURAL STREAM CHANNEL. TOP OF RIPRAP IN THE FLOOR OF THE BASIN SHOULD BE AT THE SAME ELEVATION OR LOWER THAN THE NATURAL CHANNEL BOTTOM AT SECTION " & SECTION ".

REVISIO	NS	
NAME	DATE	ILLINOIS DEPARTMENT OF TRANSPORTATION MISCELLANEOUS DETAILS
		FAP 310 (IL 255)
		SECTION 60-15
		MADISON COUNTY
		DRAWN BY EBB
		DATE CHECKED BY